

Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>A balm 18 ins. diam. bears N 5° W 2 lks. dist., marked T2N R 33 E S6 B.T. Land, mostly level. Soil, good. Timber, balm in bottom.</p> <hr/> <p>East on random between secs. 5 and 8. Variation 21° East.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at
79.80	Intersect N and S line 15 links N of cor. to secs. 4, 5, 8 and 7. Thence N. 89° 53' W on true line. Variation same.
10.00	Umatilla river 75 links at curve from S.E.
24.00	Same N.W.
35.00	Wagon Road to agency S.E. & N.W.
39.90	Set post 3 ft. long, 3 ins. square 24 ins. in the ground, marked $\frac{1}{4}$ S on N face for $\frac{1}{4}$ sec. cor., from which A balm 14 ins. diam. bears N 45° E. 150 lks. dist., marked $\frac{1}{4}$ S.B.T. A balm 4 ins. diam. bears S68°E. 40 lks. dist., marked $\frac{1}{4}$ S.B.T.
41.00	Enter brush.
79.80	Cor. to secs. 5, 6, 7 and 8. Land, bottom. Soil, 1st rate. Heavy underbrush 79.80 chains and some balm and pine timber.
	<hr/> <p>West on true line between secs. 6 & 7. Var. 21° East.</p>
7.50	Umatilla river 150 lks. S.W.
20.00	Bluff rock 10 ft. high S.W.
33.00	Bluff and reenter bottom.
40.00	A balm 4 ins. diam, which I mark $\frac{1}{4}$ S on N face for $\frac{1}{4}$.sec. corner, from which A balm 4 ins. diam. bears N40°E.40 lks. dist.,