

Chains	<p>marked $\frac{3}{4}$ S.B.T. A balm 8 ins. diam. bears S.10 W. 58 lks. dist., marked $\frac{3}{4}$ S.B.T.</p>
76.50	<p>Intersect W. bdy. Township 375 lks. N of cor. to secs. 1 and 12, T.2 N.R. 32 E. and set post 4 ft. long, 4 ins. square 24 ins. in the ground for closing cor. to secs. 6 and 7 marked C.C. T2NR32E on E. face; S6 on N and S7 on S faces with 5 notches on S and 1 notch on N edges; raised mound of stone around it. Land, bottom. Pine and balm timber and thick brush 63.50 chains.</p>
75.50	<p>North on random between secs. 5 and 6. Var. 21° East. Set temporary cors. at 20, 40 and 60 chains and at Intersect N. bdy. Township 40 lks. E. of cor. to secs. 5, 6, 31 and 32. Thence S.18' E. on true line.</p>
10.00	<p>Gulch, West.</p>
15.50	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on W face; dug pits 18 x 18 x 12 ins. N and S of post, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.</p>
26.50	<p>Wagon road, E and W.</p>
35.50	<p>Deposited charred stake 12 ins. in the ground for $\frac{3}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft.</p>
55.50	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. face.</p>