

Chains	
79.88	<p>Long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p> <p>$\frac{3}{4}$ sec. cor. between secs. 13 and 14.</p> <p>Land, level or nearly so.</p> <p>Soil, 1st rate.</p> <p>Oct. 20th, 1887.</p>
79.75	<p>East on random through N$\frac{1}{2}$ of sec. 13.</p> <p>Variation 20° East.</p> <p>Commencing at 1/16 sec. corner between secs. 13 and 14, 20 chains N. of $\frac{1}{4}$ sec. corner,</p> <p>Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary of sec. at 1/16 cor. between secs. 13 and 18,</p> <p>Thence</p> <p>West on true line.</p> <p>Variation same.</p>
8.20	<p>Wagon road N. and S.</p>
18.00	<p>Wagon road N. and S.</p>
19.94	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
39.88	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>
49.25	<p>Wagon road N and S.</p>
59.82	<p>Draw course North and S.</p> <p>Set charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, $5\frac{1}{2}$ ft.</p>