

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	between secs. 1 and 6.	
	Thence,	
	S. 89° 54' W. on true line.	
	Variation same.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.	
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S. on N. face.	
60.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner marked 1/16 S, on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base around post.	
76.00	Wagon road and canyon.	-100
80.00	Cor. of beginning.	
	Land, rolling.	
	Soil, 1st rate; some alkali.	
	East on random through N½ of sec. 1.	
	Variation 20½° East.	
	Commencing at 1/16 sec. corner 20 chains N of ¼ sec. cor., between secs. 1 and 2.	
	Set temporary corners at 20, 40 and 60 chains and at	
80.00	Intersect E. bdy. of sec. 12 lks. S. of 1/16 sec. corner between secs. 1 and 6.	
	Thence	
	S. 89° 55' W. on true line.	
	Variation same.	