

Chains	20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>	40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>	60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>Wagon road N.W.</p> <p>1/16 sec. cor. at place of beginning.</p> <p>Land, rolling.</p> <p>Oct. 21st, 1887.</p>	70.00	<p>East on random through S 1/2 of sec. 35.</p> <p>Variation 20° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains N. of S.W. cor. of sec. 35.</p> <p>Set temporary corners at 20, 40 and 60 chains and at Intersect E. bdy. of sec. 15 lks. S. of 1/16 sec. corner between secs. 35 and 36.</p> <p>Thence</p> <p>S. 89° 54' West on true line.</p> <p>Variation 21 1/2° East.</p> <p>Descend hill.</p>	80.00	<p>Deposited charred stake 12 ins. in the ground for 1/16</p>	20.00		

-200