

Sub-Subdivisions, T. 2 N., R.33 E.

Chains	
	2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
59.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.92	1/16 sec. cor. of commencing. Land, level. Soil, 1st rate.
	East on random through S½ of Sec. 26. Variation 20° East. Commencing at 1/16 sec. cor. 20 chains N of S.W. cor. of sec. 26, and Set temporary corners at 20, 40 and 60 chains, and at 79.80 Intersect E. bdy. of sec. at 1/16 sec. cor. between secs. 26 and 25. Thence West on true line. Variation same.
10.12	Wagon road N. and S.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.