

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
55.25	Dry ditch N.W.
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
79.80	To 1/16 cor. place of commencement. Land, level. Soil, 1st rate.
East on random through N½ of sec. 26.	
Var. 20° East.	
Commencing at 1/16 sec. cor. 20 chains N. of ¼ sec. cor., between secs. 26 and 27.	
Set temporary corners at 20, 40 and 60 chains and at	
79.92	Intersect E. boundary sec. at 1/16 sec. cor. between secs. 25 and 26.
Thence	
West on true line	
Variation 19° East.	
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
23.00	Wagon road, course S.W.
39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.