

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
79.90	<p>To corner of beginning.                      Land, level.                      Soil, 1st rate.</p>
80.00	<p>East on random through center of sec. 23.                      Variation 21° East.                      Commencing at <math>\frac{1}{4}</math> sec. cor. between secs. 22 and 23                      Set temporary corners at 20, 40 and 60 chains. and at                      Intersect E. boundary of sec. 14 lks. N. of <math>\frac{1}{4}</math> sec. corner.                      Thence                      N. 89° 54' W. on true line.                      Variation 19° East.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16                      sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of                      stake 5<math>\frac{1}{2}</math> ft. dist.; raised mound of earth 1<math>\frac{1}{2}</math> ft. high,                      3<math>\frac{1}{2}</math> ft. base over it and in East pit drove stake 2 ft.                      long, 2 ins. square 12 ins. in the ground marked 1/16                      S. on N. face..</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/4                      sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of                      stake 5<math>\frac{1}{2}</math> ft. dist.; raised mound of earth 1<math>\frac{1}{2}</math> ft. high,                      3<math>\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft.                      long, 2 ins. square 12 ins. in the ground marked 1/4 S.                      on N. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16                      sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of                      stake 5<math>\frac{1}{2}</math> ft. dist.; raised mound of earth 1<math>\frac{1}{2}</math> ft. high,                      3<math>\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long,                      2 ins. square, 12 ins. in the ground marked, 1/16 S. on                      N. face.</p>
80.00	<p>1/4 sec. cor. of beginning point.                      Land, level.                      Soil, 1st rate. Not cultivated.</p>

Oct. 22nd, 1887.