

Chains	
79.92	Intersect E. bdy. of sec. at cor.
	Thence
	West in true line.
	Variation 20-3/4° E.
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
23.25	Wagon road course N.
39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
42.50	Wagon road course N.
59.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
69.60	Wagon road N. and S.
79.92	To cor. of commencement.
	Land, level. Soil, good.
	East on random through center of sec. 14.
	Variation 20 1/2° East.
	Commencing at 1/4 sec. cor. between secs. 14 and 15.
	Set temporary corners at 20, 40 and 60 chains and at
79.75	Intersect E. boundary of sec. 7 lks. N. of 1/4 sec. corner
	Thence
	N. 89° 57' West on true line.
	Variation same.