

Chains	
19.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
39.87	Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S on N. face.
59.80	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins., E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.75	1/4 sec. cor. beginning point. Land, level. Soil, 1st rate. Not cultivated.
79.70	East on random through N 1/2 of Sec. 14. Var. 20° East. Commencing at 1/16 sec. corner 20 chains N. of 1/4 sec. cor. 20 chains N. of 1/4 sec. corner between secs. 14 and 15. Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary 14 lks. N of 1/16 sec. corner. Thence N. 89° 54' W on true line.
11.30	Var. same.
19.92	Wagon road N. and S. Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins.