

Sub-Subdivisions, T. 2 N., R. 33 E.

| Chains |   |                 |
|--------|---|-----------------|
| 79.90  | Intersect E. boundary 10 lks. N of 1/16 sec. corner,        |                 |
|        | Thence  |                 |
|        | N. 89° 56' West, on true line.                              |                 |
|        |   | Var. 20½° East. |
| 19.97  | Set post 3 ft. long, 3 ins. square 24 ins. in the ground    |                 |
|        | for 1/16 sec. corner, marked 1/16 S. on N. face; dug        |                 |
|        | pits 18 x 18 x 12 ins. E. and W. of post 5½ ft. dist.;      |                 |
|        | raised mound of earth 1½ ft. high, 3½ ft. base around       |                 |
|        | post.   |                 |
| 39.95  | Set post 3 ft. long, 3 ins. square 24 ins. in the ground    |                 |
|        | for 1/16 sec. corner, marked 1/16 S on N. face; dug pits    |                 |
|        | 18 x 18 x 12 ins. E. and W. of post 5½ ft. dist.; and       |                 |
|        | raised mound of earth 1½ ft. high, 3½ ft. base around       |                 |
|        | post.   |                 |
| 59.93  | Set post 3 ft. long, 3 ins. square 24 ins. in the ground    |                 |
|        | marked 1/16 S. on N. face for 1/16 sec. cor.; dug pits      |                 |
|        | 18 x 18 x 12 ins. E. and W. of post 5½ ft. dist.; raised    |                 |
|        | mound of earth 1½ ft. high, 3½ ft. base around post.        |                 |
| 72.00  | Canyon S.   | -50             |
| 79.90  | To point of beginning.                                      |                 |
|        | Land, rolling.  |                 |
|        | Soil, good. Not cultivated.                                 |                 |
|        |   |                 |
|        | Oct. 24th, 1887.  |                 |
|        | East on random through S½ of sec. 34.                       |                 |
|        |   | Var. 21° East.  |
|        | Commencing at 1/16 sec. corner 20 chains N of S.W. corner   |                 |
|        | of section 34.  |                 |
|        | Set temporary corners at 20, 40 and 60 chains, and at       |                 |
| 80.00  | Intersect E. bdy. 14 lks. N of 1/16 sec. corner,            |                 |
|        | Thence  |                 |
|        | N. 89° 54' W. on true line.                                 |                 |
|        |   | Var. 20° East.  |
| 20.00  | Deposited charred stake 12 ins. in the ground for 1/16 sec. |                 |
|        | cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft.  |                 |