

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
56.00	Dry gulch, course N.
59.74	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
79.92	To point of beginning. Land, level. Soil, 1st rate. Not cultivated. Some grass. Oct. 25th, 1887.
	East on random through center of sec. 22. Variation 20° East. Commencing at ¼ sec. cor. between secs. 21 and 22. Set temporary cors. at 20, 40 and 60 chains, and at 80.00 Intersect E. boundary 16 lks. S. of ¼ sec. cor. Thence S. 89° 53' W on true line. Variation 21° E.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
40.00	Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec.