

Chains	
20.00	<p>S. 89° 55' W. on true line.</p> <p>Variation, same.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16</p> <p>sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake</p> <p>5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft.</p> <p>base over it and in E. pit drove stake 2 ft. long, 2</p> <p>ins. square 12 ins. in the ground marked 1/16 S on N</p> <p>face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/4 sec.</p> <p>cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2</p> <p>ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base</p> <p>over it and in E. pit drove stake 2 ft. long, 2 ins.</p> <p>square 12 ins. in the ground marked 1/4 S on N face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16</p> <p>sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake</p> <p>5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft.</p> <p>base over it and in E. pit drove stake 2 ft. long, 2 ins.</p> <p>square 12 ins. in the ground marked S 1/16 on N face.</p> <p>To point of beginning.</p> <p>Land, level.</p> <p>Soil, good.</p>
80.00	<p>East on random through N 1/2 of sec. 15.</p> <p>Variation 20° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains N. of 1/4 sec. cor.</p> <p>between secs. 15 and 16</p> <p>Set temporary corners at 20, 40 and 60 chains and at</p> <p>Intersect E. bdy. 15 lks. S of 1/16 sec. cor.</p> <p>Thence</p>
79.90	<p>S. 89° 54' West on true line.</p> <p>Variation same.</p>
19.98	<p>Drove charred stake 12 ins. in the ground for 1/16 sec.</p> <p>cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2</p> <p>ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base</p> <p>over it and in E. pit drove stake 2 ft. long, 2 ins.</p>