

## Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	square 12 ins. in the ground marked 1/16 S on N face.
39.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
59.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
79.90	To point of beginning. Land, level. Soil, 1st rate. Not cultivated.
	East on random through S½ of sec. 10. Variation 20½° East. Commencing at 1/16 sec. cor. 20 chains N of S.W. corner of sec. 10 Set temporary corners at 20, 40 and 60 chains, and at
79.80	Intersect E. bdy. 16 lks. N of 1/16 sec. cor. Thence N. 89° 53' West on true line. Variation, same.
14.00	Branch 20 lks. wide, course N.W.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. & W. of stake 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
20.50	Touch grave yard.
39.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft.