

Chains	
19.98	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground                      For 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W.                      of stake 5 3/4 ft. dist.; raised mound of earth 1 3/4 ft. high                      3 3/4 ft. base around post.</p>
39.95	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground                      For 1/16 sec. corner, marked 1/16 S on N. face; dug pits                      18 x 18 x 12 ins. E. and W. of post 5 3/4 ft. dist.; and                      raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base around                      post.</p>
59.92	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground                      for 1/16 sec. cor., marked 1/16 S. on N. face; dug pits                      18 x 18 x 12 ins. E. and W. of post 5 3/4 ft. dist.; raised                      mound of earth 1 3/4 ft. high, 3 3/4 ft. base around post.</p>
65.00	<p>Canyon, course S.</p>
79.90	<p>To point of beginning.</p>
	<p>Land, rolling.</p>
	<p>Soil, 2nd rate.</p>
	<p>East on random through S 3/4 of sec. 33.</p>
	<p>Variation 20° East.</p>
	<p>Commencing at 1/16 sec. cor. 20 chains N. of S.W. cor. of                      sec. 33</p>
	<p>Set temporary corners at 20, 40 and 60 chains, and at                      Intersect E. bdy. 10 lks. N. of 1/16 sec. cor.</p>
80.00	<p>Thence</p>
20.00	<p>N. 89° 56' W. on true line.</p> <p>Variation 21° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16                      sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of                      stake 5 3/4 ft. dist., and raised mound of earth 1 3/4 ft.                      high, 3 3/4 ft. base over it and in E. pit drove stake                      2 ft. long, 2 ins. square, 12 ins. in the ground marked                      1/16 S on N. face.</p>

-250-