

Chains	
56.00	mound of earth. 1 1/2 ft. high, 3 3/4 ft. base around post.
59.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 3/4 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
79.95	To point of beginning.
	Land, level.
	Soil, 1st rate. Not cultivated. Some grass.
	Oct. 27th, 1887.
	East on random through N 1/2 of sec. 33.
	Variation 21° East
	Commencing at 1/16 sec. cor. 20 chains N of 1/4 sec. corner
	between secs. 32 and 33
	Set temporary corners at 20, 40 and 60 chains, and at
	Intersect E. bdy. 14 lks. N of 1/16 sec. corner
	Thence
	N. 89° 54' W. on true line.
	Variation 20° East
	Deposited charred stake 12 ins. in the ground for 1/16
	sec. corner; dug pits 18 x 18 x 12 ins. E. and W. 5 3/4 ft.
	dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base
	over it and in E. pit drove stake 2 ft. long, 2 ins.
	square 12 ins. in the ground marked 1/16 S on N face.
	Deposited charred stake 12 ins. in the ground for 1/16
	sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of
	stake 5 3/4 ft. dist.; raised mound of earth 1 1/2 ft. high,
	3 3/4 ft. base over it and in E. pit drove stake 2 ft. long,
	2 ins. square 12 ins. in the ground marked 1/16 S on N
	face.
	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake