

Chains	
79.95	Corner point of beginning. Land, gently rolling. Soil, good. Partly cultivated. Very little grass. Oct. 28th, 1887.
79.90	East on random through S $\frac{1}{2}$ of sec. 21. Variation 20 $\frac{1}{2}$ ° East. Commencing at 1/16 sec. corner 20 chains, North of S. W. corner of sec. 21. Set temporary $\frac{1}{16}$ sec. corners 20, 40 and 60 chains and at Intersect E. bdy. at 1/16 sec. corner. Thence
19.97	West on true line Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long. 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
39.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long. 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
59.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face. Ravine, course N.W.
63.00	