

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>East on random through $S\frac{1}{2}$ of sec. 4.</p> <p style="text-align: right;">Variation 20° East.</p> <p>Commencing at $1/16$ sec. cor. 20 chains N. of S.W. corner of sec. 4.</p> <p>Set temporary corners at 20, 40 and 60 chains, and at</p>
79.80	<p>Intersect E. bdry. 15 lks. N. of $1/16$ sec. corner,</p> <p style="text-align: center;">Thence</p> <p>N. $89^{\circ} 54'$ W. on true line.</p>
2.50	<p>Land and wagon road to Agency N. and S.</p> <p>House bears S.E. about 300 links.</p>
19.95	<p>Set post 3 ft long, 3 ins. square 24 ins. in the ground for $1/16$ sec. corner, marked $1/16$ S on N face; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.</p>
39.90	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground for $1/16$ sec. corner marked $1/16$ S on N face; dug pits 18 x 18 x 12 ins. E. and W. of post $5\frac{1}{2}$ ft. distant and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.</p>
42.25	<p>Wagon road and fence N. and S.</p>
59.85	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground for $1/16$ Sec. corner marked $1/16$ S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.</p>
79.80	<p>To point of beginning.</p> <p>Land, gently rolling.</p> <p>Soil, 1st rate.</p> <p>Not cultivated.</p>
79.92	<hr/> <p>East on random through center of sec. 4.</p> <p style="text-align: right;">Variation 21° East</p> <p>Commencing at $\frac{1}{4}$ sec. cor. bet. secs. 4 and 5</p> <p>Set temporary corners at 20, 40 and 60 chains, and at</p> <p>Intersect E. bdry. 15 lks. N of $\frac{1}{4}$ sec. corner</p> <p style="text-align: center;">Thence</p>