

## Sub-Subdivisions, T. 2 N., R. 33 E.

Chains 19.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
39.80	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
44.00	Wagon road bears N.
56.85	" " " N.
59.70	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
79.60	To the point of beginning. Land, level, or mostly. Soil, 1st rate. Some not cultivated.
	East on random through center of sec. 8. Variation 21° East Beginning at ¼ sec. corner between secs. 7 and 8 Set temporary corners at 20, 40 and 60 chains, and at
79.72	Intersect E. boundary at ½ sec. corner Thence West on true line.
14.50	Wagon road bears N. and S.
19.93	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in East pit drove stake 2 ft.