

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains		
	mound of earth and stone 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
40.25	Top of ridge bears S. Descend.	+150
46.00	Canyon, course S.	-100
59.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.	
79.92	To point of beginning. Land, level on 1st 20 chains and high, rolling hills on remainder of mile. Soil, good in bottom, rocky on hills.	
<hr/> East on random through center of sec. 5. Var. $21^{\circ}$ East.		
80.00	Beginning at $\frac{1}{4}$ sec. corner between secs. 5 and 6. Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary 25 lks. N of $\frac{1}{4}$ sec. corner Thence N. $89^{\circ} 49'$ W. on true line.	
20.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it. Descend.	
28.00	Canyon. Ascend.	-200
40.00	Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S. on N.	