

Chains	<p>high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S. G.C. on E. face. Land, gently rolling. Soil, 1st rate.</p>
20.00	<p>West on true line through N 1/2 of sec. 19. Variation 20° East.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
32.75	<p>Leave field at its S.W. corner.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18x18x12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>
76.45	<p>Intersect W. boundary Tp. 17.25 chains S. of corner to secs. 13 and 24 T. 2 N., R. 32 E., and deposited charred stake 12 ins. in the ground for 1/16 sec. closing corner; dug pits 18x18x12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S.C.C. on E. face. Land, gently rolling. Soil, 1st rate.</p>