

South Boundary of Tp. 3 N.R., 33 E.

( N. bdy. of Tp. 2 N., R. 33 E.)

Chains	
	S. 89° 46' E. on S. bdy. sec. 33. Variation 21° East.
2.30	Closing cor. secs. 32 & 33.
14.50	Gulch, course S.W.
24.75	" " " " "
39.90	To 1/4 sec. corner, a stone 15 x 7 x 6 ins., marked 1/4 on N. face, D. R. on S. face, firmly set in the ground with pits E & W., 5 1/2 ft. distant, partly filled mound mostly gone.
48.00	Gulch, course N.E.
58.40	Road " " " & S.W.
79.95	To cor. secs. 3 & 4, a stone 10 x 8 x 7 ins., firmly set on the ground marked with 3 notches on E&W edges, D.R. on S face, with pits N.E. - S.E. - S.W. & N.W. 5 1/2 ft. dist., partly filled; mound nearly gone.  Soil, ashy, 2nd rate. Land, rolling. Some grass.
<hr/>	
	S. 89° 46' E. on S. bdy. sec. 34. Variation 21° East.
1.95	Passed closing cor. secs. 33 & 34. Corner in good condition.
11.00	Gulch, course S.W.
40.00	To 1/4 sec. cor. a charred stake with pits E & W., 5 1/2 ft. dist. Stake from E. pit gone, pits and mound in good condition.
80.00	To cor. secs. 2 & 3. Post 4 ft. by 4 ins. square pulled out and put in S.E. pit. Marked S. 35, T.3, N. on N.E.; S.2 T.2 N. on S.E.; S.3, R.33 E. D.R. on S.W.; S34 on N.W. faces with 2 notches on E & 4 on W. edges, and a pit in each section 5 1/2 ft. dist. Pits and mound in fair condition. Reset post in mound.  Land, rolling. Soil, ashy & 2nd rate. Some grass.