

Topography, T. 2 N., R. 33 E.

Chains	
	Variation 21° East.
20.00	To 1/16 sec. cor. charred stake & pits.
25.50	Pendleton & La Grande Road, course N.W.
40.00	1/4 sec. corner charred stake & pits.
60.00	1/16 sec. corner, charred stake & pits.
68.00	Old Emigrant Road, course N.W. & S.E.
	Line between secs. 20 & 21. From cor. secs. 16, 17, 20 & 21. From cor. secs. 16, 17, 20 & 21, which is a charred stake with a pit in each sec. 5 1/2 ft. dist, I measured South bet. secs. 20 & 21.
	Variation 21° East
29.75	To Tудie Willow Creek, course West.
	Sec. 34.
	From 1/16 cor., 20 chs. S. of N.W. corner.
	S. 89° 51' East through North 1/2 of sec. 34.
	Variation 20° East.
17.50	Tудie Willow Creek, course N.W.
	Sec. 16.
	From cor. secs. 15-16-21 & 22, a charred stake with pit in each sec. Stake out of pit.
	N. 89° 41' W. on S. bdy. of sec. 16.
	Variation 20 1/4° East.
6.20	To Pendleton & LaGrande Road N.W. & S.E.
	From 1/16 corner 20 chains N. of S.E. cor. sec. 16, a charred stake with pits E & W 5 1/2 ft. dist.
	N. 89° 39' West through S 1/2 of sec. 16.
	Variation 2-1/2° East.
32.65	Pendleton & LaGrande Road, course N.W.
	Sec. 22 - N. 1/2
	From 1/16 cor. 20 chs. S. of N.W. cor. E. rd. and pits 5 1/2 ft. dist., N. & S. Post gone.
	N. 89° 51' E. through N 1/2 of sec. 22.