

Field Notes of Retracement-Resurvey of Subdivisional Lines, Subdivision of Section 10 and Survey of Cemeteries in said section, Township No. 2 North, Range No. 33 East, by L. E. Wilkes, under Special Instructions #29, dated Sept. 13, 1917.

CHAINS

Survey commenced Nov. 26, 1917 and executed with a Young & Sons transit No. 8585 with Smith solar attachment. For description, test and approval of instrument and method of measurements, see Book "B" of this group.

I commence at the cor. of secs. 9, 10, 15 and 16 and run N.0°25'W. for a flag on the $\frac{1}{4}$ cor. bet. secs. 9 and 10; at 20.00 chs. find no trace of the 1/16 sec. cor.; at 40.24 chs. intersect the $\frac{1}{4}$ sec. cor.; at 57.91 chains center of O.W.R.R. and N. Ry. bearing N.85°16' W. and S.85°16' E.; at 60.38 chs. the 1/16 sec. cor., reestablished by county surveyor; at 80 chs. no trace of the cor. of secs. 3, 4, 9 and 10, set temp. cor.; at 92.42 chs. S. edge of orchard, probably the garden mentioned in the field notes; at 94.67 chs. old well, 10 ft. deep, mentioned in old notes; at 99.88 chs. pass about 5 lks. W. of a house; at 101.97 chs. find no trace of 1/16 sec. cor.; at 109.40 chs. fence bears E. and W., enter road; at 121.59 chs. intersect the $\frac{1}{4}$ sec. corner between secs. 4 and 5, as recently reestablished in private survey by Geary Kimbrell, which is a basalt stone, 8x4x4 lns. above ground, marked 1/16 on W. face, and at 157.61 chs. intersect the cor. of secs. 3 and 4 on N. by. of the Tp., previously described.

I return along my random line and move the temp. cor. of secs. 3, 4, 9 and 10, N.0°25'W., 58 lks. to apportioned point for said corner. From the temp. cor. of secs. 3, 4, 9 and 10, N.89°54' W., retracing the line bet. secs. 4 and 9; at 39.65 chs. fall 31 lks. S. of the $\frac{1}{4}$ sec. cor.

From the temp. cor. of secs. 3, 4, 9 and 10, East retracing the line bet. secs. 3 and 10; at 40.00 chs. find no trace of the $\frac{1}{4}$ sec. cor., set temp. cor., and at 81.18 chs. fall 1 lk. N. of the cor. of secs. 2, 3, 10 and 11.

The cor. of secs. 2, 3, 10 and 11 is a water worn stone, 5x4x5 lns. above ground, firmly set, marked X on top, with 5 notches on S. and 2 notches on E. edge and stands on left bank of a creek, 15 lks. wide, course N.60°W. This stone was set by Geary Kimbrell in agreement with the original corner and bearing trees as same were pointed out to him by an Indian living near, and agreeing with a fence bearing N. and S.

At a point 2 lks. S. of the cor. Set an iron post, 3 ft. long, 2 lns. diam., 24 lns. in the ground, for witness cor. to the cor. of secs. 2, 3, 10 and 11, with brass cap marked