

Survey of Cemeteries in Sec.10, T. 2 N., R.33 E.

Chains

ground, for cor. No. 3, Cemetery No. 1, with brass cap  
marked

CEM 1
COR 3
1917

Thence

N.82°10' W., on S. bdy. of cemetery

2.583 Set an iron post, 3 ft. long, 1 in. diam., 26 ins. in the  
ground, for cor. No. 4, Cemetery No. 1, with brass cap  
marked

CEM 1
COR 4
1917

Thence

N.9°15'E., on W. bdy. of cemetery

2.420 To cor. No. 1, the place of beginning.  
The  $\frac{1}{4}$  cor. bet. secs. 10 and 15 bears S.16°44'W., 22.36  
chs. dist.

Area of Cemetery No. 1, 0.67 acres.

From center of sec. 10

S.44°02'E., through SE $\frac{1}{4}$  of sec. 10.

25.90 To NW. cor. No. 1 of Cemetery No. 2.

Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in  
the ground, for NW. cor. No. 1 of Cemetery No. 2, with  
brass cap marked

CEM 2
COR 1
1917

Thence

S.63°45'E., on N. bdy. of cemetery

3.425 Set an iron post, 3 ft. long, 1 in. diam., 26 ins. in the  
ground, for cor. No. 2, Cemetery No. 2, with brass cap  
marked

CEM 2
COR 2
1917

Thence

S.13°18' W., on E. bdy. of cemetery