

Tp. 2 N., R. 34 East (E. Boundary).

Chains		
40.00	Set stone 14 x 14 x 8 for $\frac{1}{4}$ Sec. corner.	
43.75	Wagon road, corner N.E. & S.W.	
80.00	Set stone 18 x 16 x 8 for corner to sections 1, 12, 6 & 7. Land, hilly. Soil, good 2nd rate. Good grass.	
<hr/> North on East boundary of Sec. 1.		
Var. 21° East.		
20.50	Foot of bluff.	-200
27.50	Umatilla River, 150 lks. flows West.	
40.00	Set post and made stone mound for $\frac{1}{4}$ Sec. cor.	
63.25	Leave river bottom.	
80.00	Set post and made stone mound for cor. to Tps. 2 & 3, N.Rs. 34 & 35 East. Soil, 1st rate. Good grass. Timber in river bottom.	
<hr/> North Boundary T. 2 N., R. 34 East W.M.		
<hr/> West on a random line bn the North boundaries of Sec- tions 1, 2, 3, 4, 5, and 6.		
Var. 19°30' East		
I set temporary half mile and mile posts at every 40 and 80 chains and 6 miles 40 links to a point 2 chains and 54 links N. of the corner to Townships 2 & 3 North Ranges 33 & 34 East.		
<hr/> North 89° 42' East on true line on North boundary of Sec. 6.		
Var. 18°30' East.		
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.	
80.00	Set post and made earth mound for corner to secs. 5, 6, 31, 32.	
Land, rolling.		
Soil, 1st rate. Excellent quality of grass.		
May 31st, 1871.		