

Subdivisions, T. 2 N., R. 34 E.

Chains	
	East on random between secs. 12 & 13. Var. 20°30' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.96	Intersected N. & S. line 14 lks. N. of corner N. 89° 54' West on true line.
39.98	Set stone 14 x 12 x 7 for $\frac{1}{4}$ Sec. corner.
79.96	To corner. Land, broken. Soil, 1st rate. Good grass.
<hr/>	
	North between Secs. 11 & 12.
40.00	Set stone, 14 x 12 x 10 for $\frac{1}{4}$ Sec. Cor.
59.50	Wagon road, course E & W.
80.00	Set stone 16 x 14 x 8 for corner to secs. 1, 2, 11, 12. Land, rolling. Soil, 1st rate. Good grass.
<hr/>	
	East on random between secs. 1 & 12. Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.94	Intersected N. & S. line 25 lks. N. of corner. N. 89° 50' West on true line.
39.97	Set stone 15 x 14 x 8 for $\frac{1}{4}$ Sec. corner.
79.94	To corner. Land, rolling. Soil, 1st rate. Good grass. June 2, 1871.
<hr/>	
	North on random between Secs. 1 & 2.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.20	Intersected North boundary 40 lks. East of corner S. 00°17' East on true line.
40.20	Set basalt stone 18 x 14 x 10 for $\frac{1}{4}$ Sec. corner.
63.50	Umatilla River, 3 chains wide, flows West.
80.20	To corner. Land, rolling. Soil, 1st rate. Good grass. Cottonwood