

Subdivisions, T. 2 N., R. 34 E.

Chains	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.84	Intersected N. & S. line at corner. West on true line.
15.50	Enter field, bears N & S.
39.92	Set post for $\frac{1}{4}$ Sec. corner, from which A Balm, 24 ins. bears N.45° E. 4 lks.
41.00	Leave field and enter river to
79.84	To corner. Land, level. Soil, 1st & 2nd rate. Bottom land subject to inundation.
<hr/>	
	West on random bet. secs. 6 & 7.
60.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.90	Intersected N. & S. line 14 S. of cor. S.89° 54' E. on true line.
39.90	Set stone 15 x 14 x 8 for $\frac{1}{4}$ Sec. cor.
60.00	Umatilla River, 250 lks., flows S.W.
79.90	To corner. Land, level. Soil, 1st & 2d rate.
<hr/>	
	North on random between secs. 5 & 6.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.14	Intersected N. boundary 20 links W. of corner. S.00° 09' W. on true line.
40.14	Set stone 18 x 12 x 12 for $\frac{1}{4}$ Sec. corner.
73.00	Umatilla River, flows S.W.
80.14	To corner. Land, rolling. Soil, 1st and 2nd rate.
June 8, 1871.	
<hr/>	
Note: I find that any corners that have been heretofore set on any portion of the Indian Reservation have been destroyed, and all the lines in my work closed so I had to rerun and establish all corners anew.	
<hr/>	