

Exteriors, T. 2 N., R. 34 East

Chains

North bet. secs. 7 & 12.

Var. 20° 30' East.

20.00 Top of mountain.

+800

40.00 Set a basalt stone 12 x 10 x 6 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins., N & S of corner, 5 $\frac{1}{2}$ ft. distant; raised earth mound 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.

80.00 Set a basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for cor. to secs. 1, 6, 7 and 12, marked 5 notches on S. and 1 on N. edges. Raised a mound of stone alongside. Pits impracticable.

Land, mountainous, 80 chs. Soil, 2nd rate. Good bunch grass. No timber.

North between Secs. 1 & 6.

Var. 20° 15' East.

34.00 Umatilla River, course W., 116 lks. wide.

-300

40.00 Set a basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on W. face, from which
 A cottonwood, 10 ins. in diam., bears N. 45° W. dist., 48 lks., marked $\frac{1}{4}$ S.B.T.
 A cottonwood, 14 ins. in diam. bears N. 80° W. dist., 34 lks., marked $\frac{1}{4}$ S.B.T.

58.00 Leave river bottom.

59.08 O. S. L. R. R. Track, course E & W.

72.73 Intersect N. bdy. 660 lks. E. of corner to Tps. 2 & 3, N.Rs. 34 & 35 East. Set a basalt stone 12x10x8 ins., 8 ins. in the ground for closing corner to Tps. 2 N. R. 34 & 35 E., marked 6 notches on S. E. & W. edges and C. C. on S. face. Raised a mound of stone alongside. Pits impracticable.

Land, mountainous, 72.73 chains. Thick underbrush along river.

Soil, 4th rate.