

Subdivisions, T. 2 N., R. 34 E.

| Chains | | |
|--------|--|------|
| 50.00 | Summit of ridge N. | +200 |
| 65.00 | Spring 35 lks. N. of line. | |
| 70.00 | Gulch N.W. | -100 |
| 80.00 | Cor. to secs. 22, 23, 26 & 27. Land, mountainous 80 chs. Soil, 1st rate. Grass, fair. | |
| <hr/> | | |
| | North bet. secs. 22 and 23. Var. 20° East. | |
| 4.50 | Old emigrant wagon road N.W. | |
| 13.80 | Gulch, N.W. | -300 |
| 40.00 | Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18x18x12 ins. N and S. of stone, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Descend gradual slope. | |
| 80.00 | Set basalt stone 16 x 10 x 8 ins., 10 ins. in the ground for cor. to secs. 14, 15, 22 and 23, marked with 3 notches on S and 2 notches on East edges; raised mound of stone over it. Pits impracticable. Land, mountains, rough, 40.00 chs. Soil, generally good. Grass, fine. Some snow brush. | |
| <hr/> | | |
| | East on random bet. secs. 14 & 23. Var. 19°50' East. | |
| 40.00 | Set temporary $\frac{1}{4}$ secs. cor. and at | |
| 79.85 | Intersect N & S line 14 lks. N. of cor. to secs. 13, 14, 23 & 24. Thence, N. 89° 54' W. on true line. Var. 19° 20' East. | |
| 7.00 | Top hill and begin to descend. | +150 |
| 24.00 | Canyon N. | -800 |
| 39.93 | Set basalt stone 12 x 8 x 6 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, dug pits 18x18x12 | |