

Subdivisions, T. 2 N., R. 34 E.

Chains		
	Land, 1st $\frac{1}{2}$ good agricultural; 2nd $\frac{1}{2}$, river bottom, brushy and rocky. Timber, cottonwood and balm along river bottom. Soil, generally 1st rate.	
	<hr/> North bet. secs. 33 and 34. <div style="text-align: right;">Var. 20° East.</div>	
40.00	Top of hill and set basalt stone 14 x 12 x 8 ins., 10 ins. in the ground marked $\frac{1}{4}$ on W. face for $\frac{1}{4}$ sec. cor.; raised mound of stone over it. Pits impracticable. Descend.	+200
55.70	Gulch N.W. Ascend.	-250
80.00	Top hill and set basalt stone 12 x 10 x 10 ins., 8 ins. in the ground for cor. to secs. 27, 28, 33 & 34, marked with 1 notch on S. and 3 notches on East edges and raised mound of stone over it. Pits impracticable. Land, rough and mountainous 80 chs. Soil, rocky, 4th rate. Bunch grass, good.	
	<hr/> East on random bet. secs. 27 & 34. <div style="text-align: right;">Var. 20$\frac{1}{4}$° East.</div>	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.75	Intersect N & S line 25 lks. N. of cor. to secs. 26, 27, 34 & 35.	
	<div style="text-align: center;">Thence</div> North 89° 49' W. on true line. <div style="text-align: right;">Var. 21° East.</div>	
7.50	Ascend. Top ridge, N.	+200
30.00	Canyon, N.	-200
32.00	Summit spur N.	+50
37.00	Gulch, N.	-50