

Subdivisions, T. 2, N., R. 34 E.

Chains		
40.38	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, from which A pine, 12 ins. in diam. bears N. 45° W. 40 lks. dist., marked $\frac{1}{4}$ S. B. T. A pine, 12 ins. in diam., bears S. 70° E. 25 lks. dist., marked $\frac{1}{4}$ S. B. T.	
43.00	Top of hill N.	+250
48.00	Gulch, N.	-200
72.50	Summit ridge N.W.	+100
80.75	Cor. to secs. 27, 28, 33 and 34. Land, extremely rough, broken, 80.75 chs. Very brushy and some pine timber in canyons and on N. sides of hills. Soil, 4th rate.	
Sept. 2d, 1887.		
<hr/> North bet. secs. 27 and 28.		
Var. 20 $\frac{1}{4}$ ° East.		
34.00	Gulch, N.W.	
40.00	Set basalt stone 20 x 10 x 7 ins., 14 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face and raised a mound of stone over it. Pits impracticable.	
43.50	Spring 150 lks. E. of line.	
80.00	Set basalt stone 18 x 14 x 12 ins., 12 ins. in the ground for cor. to secs. 21, 22, 27 & 28, marked with 2 notches on S. and 3 notches on E. edges and raised mound of stone over it. Pits impracticable. Land, rough and mountainous 80 chs. Soil, rocky, 4th rate. Bunch grass, good.	
<hr/> East on ran. bet. secs. 22 and 27.		
Var. 21-3/4° East.		
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.50	Intersect N and S line 50 lks. N of cor. to secs. 22, 23, 26 & 27,	