

Subdivisions, T. 2 N., R. 34 E.

Chains		
	<p style="text-align: center;">Thence</p> <p>N. 89° 39' W. on true line.</p> <p style="text-align: right;">Var. 20° East.</p>	
5.00	Top of ridge N.	+200
32.00	Gulch, N.	-300
40.25	Set basalt stone, 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; raised mound of stone over it. Pits impracticable.	
48.25	Gulch, N.W.	
80.50	Cor. to secs. 21, 22, 27 & 28.	
	Land, very rough and mountainous 80.50 chs.	
	Soil, 4th rate. Bunch grass.	
North bet. secs. 21 & 22.		
	Var. 21° 45' East.	
12.00	Top mountain N.W. and begin descent.	
40.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N & S of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
52.50	Dry bed of creek N.W.	-300
80.00	Set basalt stone 18 x 18 x 7 ins., 12 ins. in the ground for cor. to secs. 15, 16, 21 & 22, marked with 3 notches on S. & E. edges, raised mound of stone over it. Pits impracticable.	
	Land, mostly rolling.	
	Soil, 1st rate. Grass, good.	
East on ran. bet. secs. 15 & 22.		
	Var. 19° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.05	Intersect N and S line 21 lks. N. of cor. to secs. 14, 15, 22 & 23,	
	Thence	
	N. 89° 51' W. on true line.	