

## Subdivisions, T. 2 N., R. 34 E.

Chains	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on West face.
21.90	Wagon road E & W.
40.00	Set basalt stone 16 x 8 x 5 ins., 10 ins. in the ground for ¼ sec. cor., marked ¼ on W. face and raised mound of stone over it. Pits impracticable.
43.00	Gulch, W.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of cor. 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
77.50	Wagon road E & W.
80.00	Deposited charred stake 12 ins. in the ground for cor. to secs. 3, 4, 9 & 10; dug pits 18 x 18 x 12 ins. in each sec. 5½ ft. dist.; raised mound of stone and earth 2 ft. high, 4½ ft. base over it and in S.E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked T 2 N Sec. 3 on N.E.; R 34 E. S.10 on S.E.; S.9 on S.W. and S.4, on N.W. faces, with 5 notches on S. and 3 notches on E. edges.
	Land, slightly rolling.
	Soil, 2nd rate. Some small gravel and shell rock. Fair for agriculture. Grass, good.
	East on ran. bet. secs. 3 & 10.
	Var. 19½° East.
	Set temporary cors. at 20, 40, & 60 chs., and at
79.75	Intersect N and S line 50 lks. N of cor. to secs. 2, 3, 10 & 11,
	Thence