

Subdivisions, T. 2 N., R. 34 E.

Chains	<p>18 x 18 x 12 ins. N &amp; S of post 5<math>\frac{1}{2}</math> ft. dist. and raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{3}{4}</math> ft. base over it.</p> <p>Ascend gradual slope.</p>	
60.00	<p>Set stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on W. face and raised mound of stone over it. Pits impracticable.</p>	
74.25	<p>Intersect Tp. line 7.25 chs. E. of cor. to secs. 33 &amp; 34, T. 3 N. R. 34 E. and deposited charred stake 12 ins. in the ground for closing cor. to secs. 3 &amp; 4; dug pits 18 x 18 x 12 ins. S., E., &amp; W. of stake, 5<math>\frac{1}{2}</math> ft. dist.; raised mound of earth 2 ft. high, 4<math>\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked C. C. T 2 N R 34 E on S.; S 3 on E and S 4 on W. faces, with 3 notches on E &amp; W edges.</p> <p>Land, last <math>\frac{1}{2}</math> mile can be cultivated; first <math>\frac{1}{2}</math>, river bottom and bluffs.</p> <p>Soil, fair. No grass.</p>	
<hr/>		
	<p>From cor. to secs. 4-5-32 &amp; 33 on the S. bdy. of Township,</p> <p>I run</p> <p>North bet. secs. 32 &amp; 33.</p> <p style="text-align: right;">Var. 19° East</p>	
6.15	Trail W.	
10.00	Summit, West.	†40
30.00	Canyon N.W.	-150
40.00	Set stone 16 x 12 x 10 ins., 10 ins. in the ground marked $\frac{1}{4}$ on W. face for $\frac{1}{4}$ sec. cor.; raised mound of stone over it. Pits impracticable.	
48.00	Canyon N.W.	-60
60.00	Summit ridge & trail N.W.	†100
65.70	Ravine E.	-40
80.00	Set stone 14 x 10 x 8 ins., 9 ins. in the ground for cor. to secs. 28, 29, 32 and 33, marked with 1 notch on S. and 4 notches on E. edges and raised a mound of stone	†20