

Subdivisions, T. 2 N., R. 34 E.

Chains	
20.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 on W. face; dug pits 18 x 18 x 12 ins. N & S. of cor. 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.
24.00	Enter Indian field E & W.
40.00	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for ¼ sec. cor., marked ¼ on W. face; dug pits 18 x 18 x 12 ins. N & S of stone 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in North pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W face.
73.69	Dry ditch N.W.
77.69	Enter field E & W.
80.00	Set basalt stone 16 x 8 x 7 ins., 11 ins. in the ground for cor. to secs. 8, 9, 16 and 17, marked with 4 notches on S and E. edges; dug pits 18 x 18 x 12 ins. in each sec. 5½ ft. dist. and raised mound of earth 2 ft. high, 4½ ft. base over it.
	Land, rolling.
	Soil, 1st rate. Good bunch grass. Partly cultivated.
	East on ran. bet. secs. 9 and 16.
	Var. 21-3/4° East
	Set temporary cors. at 20, 40, & 60 chs. and at
79.50	Intersect N and S line at cor. to secs. 9, 10, 15 & 16.
	Thence,
	West on true line.
	Var. same.
19.87	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor, marked 1/16 on N face and raised mound of stone over it. Pits impracticable.
39.75	Set basalt stone 14 x 10 x 5 ins., 10 ins. in the ground