

Subdivisions, T. 2 N., R. 34 E.

Chains		
80.00	<p>Cor. to secs. 29, 30, 31 and 32.</p> <p>Land, high, rough, and mountainous 80 chains.</p> <p>Soil, 1st rate on N. hill sides. Grass, good. No timber. Only fit for grazing.</p>	
<hr/> <p>West on ran. bet. secs. 30 & 31.</p> <p style="text-align: right;">Var. 21° East.</p>		
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
84.70	Intersect Tp. line at cor. to secs. 25, 36, 30 & 31.	
<p style="text-align: center;">Thence</p> <p>East on true line.</p> <p style="text-align: right;">Var. 21-3/4° East</p>		
Ascend.		
17.00	Summit and trail N.	+100
Descend steep hillside.		
36.50	Canyon N.	-200
Ascend.		
44.70	Set basalt stone 20 x 18 x 10 ins., 15 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N face; raised mound of stone over it. Pits impracticable.	
56.00	Summit ridge N.	+300
Descend.		
84.00	Canyon.	-300
84.70	<p>Cor. to secs. 29, 30, 31 & 32.</p> <p>Land, high and badly broken, mountainous 84.70 chs.</p> <p>Soil, 3rd rate, generally. Good bunch grass.</p>	
<hr/> <p>North bet. secs. 29 & 30.</p> <p style="text-align: right;">Var. 21° East.</p>		
7.50	Draw, W.	-20
35.00	Summit ridge N.W.	+200
Descend.		
40.00	<p>Set basalt stone 18 x 12 x 6 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18x18x12 ins., N & S of stone 5$\frac{1}{2}$ ft. dist., and raised mound of stone and earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p>	