

Subdivisions, T. 2 N., R. 34 E.

Chains 79.25	Cor. to secs. 17, 18, 19 & 20. Land, mostly rolling. Soil, 1st rate. Well adapted to agriculture.	
84.00	West on random bet. secs. 18 & 19. <span style="float: right;">Var. 21° East.</span> Set temporary cors. at 20, 40 and 60 chs. and at Intersect Tp. line 42 lks. N. of cor. to secs. 13 & 24, 18 & 19.	C
24.00	Thence, N. 89° 43' East on true line. Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5½ ft. dist.; raised mound of stone and earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 on N. face.	D
31.50	Dry gulch N.	-20
44.00	Set basalt stone 16 x 12 x 8 ins., 10 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stone 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.	
60.25	Dry gulch N.E.	-75
63.00	Wagon road N.E.	
64.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 on N. face.	E
84.00	Cor. to secs. 17, 18, 19 and 20. Land, rolling. Soil, 1st rate.	
20.00	North bet. secs. 17 & 18. <span style="float: right;">Var. 21° East.</span> Drove charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base	