

## South Boundary of T. 3 N., R. 35 E.

Chains		
40.00	Set $\frac{1}{4}$ section corner. Set stone, 6x10x14, basalt, on hillside facing the South.	-10
80.00	Set basalt stone, 6x12x15. Corner for sections 33, 34, 3 and 4. Land, broken and stony.	
East on South boundary of section 34. Var. 19° East.		
25.00	Enter timber in river bottom.	-130
31.50	Umatilla River, 3.00 chs. wide, course South West.	
40.00	Set post corner for $\frac{1}{4}$ section, from which, A balm, 6 ins. diam., bears N.19°E., 75 lks. " " 24 " " " S.87°E., 37 lks.	
63.50	Stage Road, course N.E. and S.W.	
70.00	Leave timber and river bottom.	
80.00	Set post corner for sections 34, 35 and 2 and 3, from which, A pine, 5 ins. diam., bears N.46°E., 156 lks. " " 6 " " " N.87°E., 100 lks. No other tree near. Dug pits, and raised mound as per instructions. Land, broken except in river bottom all stony. Timber, balm, pine and alder. Undergrowth the same. July 27.	+80
East on South boundary of section 35. Var. 21° East.		
40.00	Set post corner, for $\frac{1}{4}$ section, drove charred stake. Dug pits and raised mound as per instructions.	+30
62.00	A pine tree, 18 ins. diam., Var. 20°30' East.	+120
80.00	Set basalt stone, 6x10x16, for corner to sections 35, 36, 1 and 2. Land, broken. Good grass. Soil, 2nd rate.	-100