

East Boundary of T. 2 N., R. 35 E.

Chains		
55.00	Top of ridge.	+300
69.00	Gulch, course E.	-150
80.00	Set a basalt stone, 12x9x7 ins., 8 ins. in the ground, for cor. to secs. 7, 12, 13 and 18, marked 4 notches on S. and 2 on N. edges. Raised a md. of stone alongside. Pits impracticable. Land, exceedingly rough and mountainous. 80 chs. Soil, rocky, 4th rate. No timber, poor grass.	
North on East bdy. sec. 12.		
	Var. 16°E.	
10.00	Gulch, course E.	-200
22.00	Ridge, course E.	+250
30.00	Gulch, course E.	-200
40.00	Set a basalt stone, 10x9x8 ins., 7 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face. Raised md. of stone alongside. Pits impracticable.	
50.00	Gulch, course E.	-200
65.00	Ridge, course E.	+120
80.00	Set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for cor. to secs. 1, 6, 7 and 12, marked 5 notches on S. and 1 on N. edges. Raised a md. of stone alongside. Pits impracticable. Land, mountainous. 80 chs. Soil, rocky, 4th rate. No timber. Poor grass.	
North on E. bdy. sec. 1.		
	Var. 21°15'E.	
15.00	Gulch, course E.	-50
30.00	Summit of divide.	+1000
40.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ cor. marked $\frac{1}{4}$ on W. face. Raised md. of stone alongside. Pits impracticable.	
50.50	Gulch, course W.	-200