

South Boundary of T. 3 N., R. 35 E.

Chains 80.00	<p>Set a post, 48x4x4 ins., 12 ins. in the ground, for cor. to secs. 31 and 32, marked T 3 N S 31 on N.W., R 35 E S 32 on N.E., T 2 N on S., with 5 notches on E. and 1 notch on W. edges, from which,</p> <p>A balm tree, 8 ins. diam., bears N.85°E., dist. 81 lks., marked T 3 N R 35 E S 32 B T.</p> <p>A balm, 16 ins. in diam., bears N.50°W., dist. 34 lks., marked S 31 B T.</p> <p>Land, level bottom.</p> <p>Soil, gravelly, 4th rate.</p> <p>Balm and pine timber, and dense underbrush. 80.00 chs.</p>	
<p>19.50</p> <p>23.00</p> <p>32.50</p> <p>40.00</p> <p>40.70</p> <p>50.00</p> <p>55.00</p> <p>80.00</p>	<p>South 89°50'W. on S. bdy. sec. 31.</p> <p style="text-align: center;">Var. 20°15'E.</p> <p>Umatilla River, 300 lks. wide, course S.80°W.</p> <p>Leave river bottom.</p> <p>Summit of ridge.</p> <p>Set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Raised a mound of stone alongside. Pits impracticable.</p> <p>Draw, course S.</p> <p>Ridge, course S.</p> <p>Draw, course S.</p> <p>To cor. to Tps. 3 N., R. 34 and 35 E.</p> <p>Land, mountainous.</p> <p>Soil, rocky, 4th rate.</p> <p>Dense brush in river bottom. 80.00 chs.</p> <p style="text-align: right;">August 25, 1887.</p>	<p>+150</p> <p>+50</p> <p>-50</p>
	<p style="text-align: center;">August 25, 1887.</p> <p style="text-align: center;">Set a post on the N.W. cor.</p>	