

Subdivisions of T. 2 N., R. 35 E.

Chains		
40.00	Set a stone, 8x10x16 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
43.00	Top of ridge, course E. Descend brushy hillside.	
55.00	Canyon, course East. Ascend.	-400
80.00	Set a stone, 8x12x24 ins., 16 ins. in the ground, for cor. to secs. 10, 11, 14 and 15 marked with 4 notches on S. and 2 on E. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, extremely rough and mountainous. 80 chs. Bunch grass good. Some scattering pine timber in canyons. Soil, 4th rate.	
	East on random between secs. 11 and 14. Var. $21^{\circ}45'$ East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
79.70	Intersect N. and S. line, 30 lks. S. of cor. to secs. 11, 12, 13 and 14. Thence S. $89^{\circ}47'$ West on true line.	
23.25	Creek, 25 lks. wide, course N. Ascend.	-60
39.85	Set a stone, 7x10x18 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
45.00	Summit of ridge.	
79.70	To cor. to secs. 10, 11, 14 and 15. Soil, 3rd rate. Land, mountainous. 79.70. Some bunch grass.	