

Subdivisions of T. 2 N., R. 35 E.

Chains	North on true line between secs. 10 and 11. Var. 21°45'East. Descend gradual sloping ridge.	
40.00	Set basalt stone, 17x18x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
80.00	Set a stone, 17x18x9 ins., 6 ins. in the ground, for cor. to secs. 2, 3, 10 and 11 marked with 5 notches on S. and 2 on E. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. This line runs along a gently sloping ridge. Soil, stony and 4th rate. Some bunch grass.	
	East on random between secs. 2 and 11. Var. 21°45'East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
79.50	Intersect N. and S. line at cor. to secs. 1, 2, 11 and 12. Thence West on true line.	
13.75	Gulch or canyon, course N.W.	-300
20.00	Creek, course N.E.	-450
23.25	Leave creek bottom; and ascend.	
39.75	Set a basalt stone, 4x10x12 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
71.25	Top of mountain.	
79.50	To cor. to secs. 2, 3, 10 and 11. Land, very mountainous. 79.50 chs. Timber on creek, pine and fir. Good grass. Soil, 3rd rate.	
	North on true line between secs. 2 and 3. Var. 21°15'East.	