

Subdivisions of T. 2 N., R. 35 E.

Chains 51.00	Canyon, course N.E. Ascend.	-200
80.00	Set a stone, 8x10x20 ins., 14 ins. in the ground, for cor. to secs. 15, 16, 21 and 22 marked with 3 notches on E. and S. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. On E. side of long ridge running N. and S. Land, rough and mountainous. 80 chs. Good grass. Soil, 3rd rate.	
	East on random between secs. 15 and 22. Var. 21° East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
80.20	Intersect N. and S. line, 15 lks. S. of cor. to secs. 14, 15, 22 and 23. Thence S. 89°54'W. on true line.	
20.00	Top of ridge, course S.E.	+600
33.50	Canyon, course S.E.	-100
40.10	Set a stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	+150
46.50	Gulch, course S.E.	-200
52.00	Summit of ridge.	+1000
65.00	Canyon, course N.W.	-500
80.20	To cor. to secs. 15, 16, 21 and 22. Land, rough, mountainous. 80.20 chs. Soil, poor and rocky. Bunch grass.	
	North on true line between secs. 15 and 16. Var. 21° East.	
	Descend.	
25.00	Canyon, course N.W. Ascend.	-800