

Subdivisions of T. 2 N., R. 35 E.

Chains 40.00	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base around post. Pits impracticable.	
60.00	Top of ridge, course N.W.	+750
66.00	Gulch, course N.W.	-300
80.00	Set a stone, 12x12x16 ins., 10 ins. in the ground, for cor. to secs. 9, 10, 15 and 16 marked with 4 notches on S. and 3 on E. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, rough and mountainous. 80 chs. Soil, 4th rate and rocky. Bunch grass. September 9, 1887.	
	East on random between secs. 10 and 15. Var. 21° East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
79.75	Intersect N. and S. line, 28 lks. S. of cor. to secs. 10, 11, 14 and 15. Thence S. 89° 48' W. on true line.	
10.00	Summit of ridge, course N.	+800
32.00	Canyon, course N.	-600
39.87	Set a stone, 17x18x9 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
52.00	Summit of ridge, course N.	+500
79.75	To cor. to secs. 9, 10, 15 and 16. Land, rough and mountainous. 79.75 chs. Soil, 3rd rate. Good grass.	
	North on true line between secs. 9 and 10. Var. 20° East.	
26.00	Gulch, course N.W.	-350