

## Allotments of T. 2 N., R. 35 E.

Chains	Sec. 4	
	From the 1/16 sec. corner, 10 chs. E. and 5 chains N. of $\frac{1}{4}$ sec. cor. in the center of sec. 4.	
	I run	
	East on true line in sec. 4.	
	Var. 18° East.	
	Through grain.	
17.50	Leave grain field.	
19.00	Descend bluff.	-30
20.00	Set post 3 ft. long, 3 ins. sq., 24 ins. in the ground, for 1/16 sec. corner marked 1/16 S on N. face, from which,	
	A thorn, 5 ins. diam., bears N.45°W., 12 lks. dist., marked 1/16 S B T.	
	A balm, 8 ins. diam., bears N.40°E., 20 lks. dist., marked 1/16 S B T.	
	Land, rolling.	
	Soil, 1st rate.	
	Grain and grass. Little timber.	
<hr/>		
	From the 1/16 sec. corner, 5 chs. N. and 30 chs. East of $\frac{1}{4}$ sec. corner in the center of sec. 4.	
	I run	
	South on true line in sec. 4.	
	Var. 20° E.	
.65	Bluff.	+30
12.00	Fence, course E. and W.	
	Gulch, N.E. of line about 3.50 chains parallel.	
15.00	Set post 4 ft. long, 5 ins. square with marked stone 12 ins. in the ground, for 1/16 sec. corner marked 1/16 S on W. face. Dug pits, 18x18x12 ins., N. and S. of post, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.	
	Land, rolling.	
	Soil, 1st rate.	
	Good grass.	