

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 5
	<p>N.E., R 35 E S 8 on S.E., S 7 on S.W. and S 6 on N.W. faces, with 5 notches on S. and E. edges, with pits, 18x18x12 ins. in each sec. 5½ ft. dist. and mound of earth 2 ft. high, 4½ ft. base around post.</p>
	<p>I run North on random line between secs. 5 and 6. Var. 20°30'E.</p>
40.00	<p>Setting temporary 1/32 sec. cor. at 20.00 chains, and at Intersect line at ¼ sec. corner between secs. 5 and 6.</p>
	<p>Thence I run South on true line between secs. 5 and 6. Var. 20°E.</p>
20.00	<p>Ascend to Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for 1/32 sec. corner marked 1/32 S on W. face. Dug pits, 18x18x12 ins., N. and S. of post, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base around post.</p>
40.00	<p>To the corner to secs. 5, 6, 7 and 8. Land, west slope. Grass, sunflowers and some brush.</p>
	<p>From 1/16 sec. corner 20 chs. E. of ¼ sec. corner between secs. 5 and 6. I run South on true line in sec. 5. Var. 21°E.</p>
4.00	<p>Ascend. Fence, course E. and W.</p>
10.00	<p>Set post 4 ft. long, 3 ins. sq. with large cone 24 ins. in the ground, for 1/32 sec. corner marked 1/32 S on W. face. Dug pits, 18x18x12 ins., N. and S. of post, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base around post. Land, rolling. Soil, 1st rate. Grass and sunflowers.</p>