

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 5	
	N.89°42'E. on true line between secs. 5 and 8.	
	Var. 21°E.	
10.00	Set stone, 9x8x7 ins., 6 ins. in the ground, for 1/32 sec. corner marked 1/32 on N. face, and raised a mound of stone over it. Pits impracticable.	
	Line over brow to summit of Mountain.	
	Soil, 1st rate.	
	Good grass.	
	Sec. 6	
	From the 1/4 sec. corner between secs. 5 and 6.	
	I run	
	West on true line in sec. 6.	
	Var. 21°East.	
12.00	Wire fence, course N.	
12.40	Gulch, course N.	
13.00	Rail fence, course N.	
20.00	Set post 3 ft. long, 3 ins. square, with marked stone 12 ins. in ground, for 1/16 sec. corner marked 1/16 S on N. face. Dug pits, 18x18x12 ins., E. and W. of post, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base around post.	
	2.00 chs. W. of this corner is a fence, N.W.	
	Land, rolling.	
	Soil, 1st rate.	
	Good grass.	
	From 1/16 sec. corner, 20 chs. W. of 1/4 sec. corner between secs. 5 and 6.	
	I run	
	North on true line in sec. 6.	
	Var. 20°E.	
12.50	Bluff, course E. and W.	+100
14.50	Railroad, course S.80°W.	
18.50	Spring branch, 10 lks. wide, course W.	