

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 6
20.00	<p>Set post, 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner marked 1/16 S on S. face, from which,</p> <p>A balm, 36 ins. diam., bears S.30°W., 4 lks. dist., marked 1/16 S B T.</p> <p>A balm, 8 ins., diam., bears N.20°E., 18 lks. dist., marked 1/16 S B T.</p> <p>Land, rolling to the bluff, rich bottom and gravelly from bluff N.</p> <p>Grass and grain on hill.</p> <p>Timber and brush on bottom.</p>
40.00	<p>From the corner to secs. 5, 6, 7 and 8.</p> <p>I run</p> <p>N.89°37'West on random line between secs. 6 and 7.</p> <p style="text-align: center;">Var. 21°E.</p> <p>Setting temporary corner at 20 chs., and at</p> <p>Intersect the 1/4 sec. corner between secs. 6 and 7, which is a stone, 16x10x8 ins., 10 ins. in the ground, marked 1/4 on N. face, with pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p> <p>Thence I run</p> <p>S.89°37'E. on true line between secs. 6 and 7.</p> <p style="text-align: center;">Var. 23°E.</p>
6.50	Summit, course N.
20.00	<p>Set stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 and 1/32 sec. corner, marked 1/16 on S. and 1/32 on N. face.</p> <p>Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p>
40.00	<p>The corner to secs. 5, 6, 7 and 8.</p> <p>Land, mountainous.</p> <p>Soil, rich on West side of summit, balance 1st rate.</p> <p>Grass.</p>