

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 7
	<p>Land, mostly rocky. Soil is 1st rate on part. Grass and sunflowers.</p>
	<p>From the 1/16 sec. corner, 20 chs. S. of $\frac{1}{4}$ sec. corner between secs. 6 and 7.</p> <p>I run East on random line in sec. 7. Var. 22°E. Setting temporary corner at 20 chains, and at</p>
40.00	<p>Intersect N. and S. line at 1/16 sec. corner between secs. 7 and 8.</p> <p>Thence I run West on true line in sec. 7. Var. 19°E.</p>
20.00	<p>Set basalt stone, 12x9x7 ins., 8 ins. in the ground, for 1/16 and 1/32 sec. corner marked 1/16 on N. and 1/32 on S. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
40.00	<p>To the 1/16 sec. corner. Land, rolling. Soil, 1st and 2nd rate. Good grass.</p>
	<p>From the 1/32 sec. corner, 30 chs. S. of $\frac{1}{4}$ sec. corner between secs. 6 and 7.</p> <p>I run East on random line in sec. 7. Var. 22°East. Setting temporary corner at 20 chs., and at</p>
40.00	<p>Intersect N. and S. line at 1/32 sec. corner, 10 chs. N. of $\frac{1}{4}$ sec. corner between secs. 7 and 8.</p> <p>Thence I run West on true line in sec. 7. Var. 19°E.</p>